

S.no	Item.no	Description of item	Unit	Quantity	Rate including all taxes	Amount	Remarks
1	6.2	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) :					
	6.2.1	With F.P.S.(non modular) bricks	cume c	0.3	8030.6	2409.18	
2	6.13	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.					
	6.13.2	Cement mortar 1:4 (1 cement :4 coarse sand)	Sqm	0.1	1018.05	101.805	
3	5.22A	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.					
	5.22A.1	Mild steel and Medium Tensile steel bars	KG	22	88.95	1956.9	
4	5.9.4	Centering and shuttering including strutting, propping etc. and removal of form for					
	5.9.4	Shelves (Cast in situ)	Sqm	3	766.55	2299.65	
5	5.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	cume c	0.25	10719.3	2679.825	

6	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement,					
	8.2.2	Granite of any colour and shade					
	8.2.2.2	Area of slab over 0.50 sqm	Sqm	2.5	4425.35	11063.38	
7	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc.,including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.					
	8.3.2	Granite work	Rmtr	5	418.85	2094.25	
8	11.37	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	Sqm	0.5	935.6	467.8	
Total Amount in Rs						23073	